

## Rules on site supervision, vehicle washing and possible pedestrian access routes

<b>Emitted by:</b>	<b>PH Movimento</b>
<b>Volume of Safety Rules:</b>	<b>4 – Airside Construction Sites</b>
<b>Ref. Par.:</b>	<b>4.1.11 - 4.1.12 - 4.2.6 - 4.2.7</b>

*Sections 4.1.11 - 4.1.12 - 4.2.6 - 4.2.7 is updated as follows.  
(changes/added text highlighted in grey)*

**4.1.11.** The operational safety ADR-ISE may request, by specifying it in the VAL (Form F01 'Control of Works - site handover'), continuous assistance for aspects of site safety which may fall to the Project Manager or the RUP/ Construction Manager for the entire duration of the site.

**4.1.12.** Technical supervision by the Project Manager or RUP/Construction Manager must be provided for all critical phases of the construction site.

**4.2.6.** The Contractor is responsible for ensuring that the vehicles used on site are washed before leaving the site to reduce the risk of FOD generation outside the area, in particular on the access/exit route to the site area.

**4.2.7** Due to the location of the construction site, it is possible to provide walking access to the construction site for which a verification of suitability must be carried out by ADR-ISE Operational Safety and be provided for in the VAL (Form F01 'Control of Work - Construction Site Delivery').